


- NOTES**
1. MULTI-UNIT RESIDENTIAL DEVELOPMENTS SHALL BE DESIGNED WITH A TRIPLE-WIDE ENCLOSURE TO ACCOMMODATE THREE COMMODITIES FOR RECYCLING.
 2. TRIPLE-WIDE ENCLOSURES SHALL HAVE A NET ENCLOSURE OPENING OF 36 FEET AND SHALL BE DESIGNED WITHOUT MIDWALLS. GATES, HINGES, AND MOUNTING HARDWARE SHALL NOT INTRUDE UPON MINIMUM NET ENCLOSURE OPENING.
 3. GATES, HINGES, AND MOUNTING HARDWARE SHALL BE INSTALLED SO THERE IS A MINIMUM 9 FOOT DEPTH CREATED WITHIN EACH ENCLOSURE.
 4. BIN ENCLOSURES ARE TO BE ANGLED NO MORE THAN 30 DEGREES FROM THE CENTER LINE OF THE SOLID WASTE COLLECTION VEHICLE ROUTE.
 5. CONTRACTION JOINTS MAY BE EITHER SCORED OR SAWCUT 1-INCH DEEP.



TRIPLE-WIDE BIN ENCLOSURE
N.T.S.